## Addendum No. 3

Controlled Access - Wireless Access Modular System

Wireless OmniLock module to be installed on this door.

The three exterior doors including the interior lobby door will be access controlled and they will require a wireless lock to be installed.

The existing server that is located in the existing building will be moved to the data room in this new building. There will be a conduit running from the new station to the existing station that will have data cable and station alerting wiring connecting both buildings.

The current RFP specifies a wireless access modular control access system for the new building.

We have indicated to the bidders that COR Security Systems is the sole source vendor for the district and they will communicate directly with the vendor regarding the control access system requirements and installation.



Wireless OmniLock module to be installed on these doors.

Wireless Omni-Lock module to be installed next to interior lobby door.

RANCHO SANTA FE FIRE STATION NO. 6

PROPOSED FLOOR PLAN

BUILDING: APPROXIMATELY 2,500 S.F. 01/04/2018

SCALE: 1/4" = 1'-0"